



**OFFICE OF THE PRINCIPAL, GOVERNMENT ENGINEERING COLLEGE  
BILASPUR (C.G.) 495 009.**

(Approved by AICTE, Affiliated by CSVTU)

Phone: 07752-260339, Email: [principalgecbilaspur@gmail.com](mailto:principalgecbilaspur@gmail.com)

Ref. No. : GECB/*skno/ 408* /...../Bilaspur

Date: *14* / *2* /2024

To,

Address see overleaf

Sub:- Quotation for supply of CCTV.

Please quote your lowest rate for the supply of the CCTV system/equipment. Quotation should be addressed to the Principal, Govt.Engg.College, Bilaspur C.G.-495009 in sealed envelope and reach to this office on or before 28/02/2024 at 12:00 P.M. On the top of the envelope please write quotation against enquiry number as above.

1. GST applicable as per rule.
2. Quotation should be valid for the period of Twelve Months from the due date
3. Payment will be made after the installation of cctv working/good condition.
4. Leaflet containing particulars & literature should be furnished along with the quotation.
5. It is not binding on the purchase to accept any of the lowest rate of the quotaion & no reason will be assigned for the same.
6. Sales Tax & income Tax clearance must be enclosed along with the quotation.
7. GST number should be mentioned in your quotation, photocopy of GST & PAN Card should be attached.
8. List of the Equipments is attached on the back side.
9. All Equipments/Materials should bear a guarantee of 12 Months.
10. Rate of items should be quoted in enclosed proforma and rate of GST should be mentioned for each item separately.
11. All Price quoted should be F.O.R. this institute and they should be quoted separately for each item asked.
12. Disputes are subjected to the Jurisdiction of Bilaspur Court.


  
Principal

Govt Engg College  
Bilaspur



**Technical specification for CCTV**

S.N.	Name of Equipment / Item	Specification	Quantity
1	16 channel NVR	16 channel, SATA interface upto 4TB supported, IP camera supported	1 No.
2	IP camera	IP, resolution -4 MP, auto day night switch, IR range-30 mtr, video compression H.265+, Ethernet connectivity, inbuilt Mic,	12 Nos.
3	Switch port	8+2 POE switch, plug and play installation, 10/100 Mbps ethernet	2
4	Hard disk	2 TB SATA	1
5	Rack	4 U rack	1
6	Switch port	8 port	1
7	Cat 6 cable	2 bundle (305 mtr)	2 bundle
8	Installation and services		

  
Principal  
Govt Engg College  
Bilaspur